



March 22, 2021

Village of Middleville
Patricia Rayl
Village Manager
100 East Main Street
Middleville, MI 49333

CONTRACT: 2021 WWTP EXPANSION AND IMPROVEMENTS PROJECT

ADDENDUM No. 2

Notice to All Prospective Bidders:

This Addendum is issued in accordance with SECTION 00 20 00 - INSTRUCTIONS TO BIDDERS, and is hereby incorporated into the Contract Documents. The CONTRACTOR is reminded to appropriately-acknowledge receipt of this Addendum in SECTION 00 42 00 - PROPOSAL. *This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated March 5, 2021. This Addendum No. 1 consists of two (2) typed pages. The issue of the Specification Sections, and the issue of Drawings are listed at the end of this document and are attached to this document.*

Answers to Written Questions

1. Davis Bacon Act does not apply to this project.
2. Quantities for solids to be removed from the Polishing Pond, sludge storage tank, and SBRs have been added to the Bid Form in Addendum No. 1.
3. The OWNER will lower the Polishing Pond through the RIB system.
4. Testing data on the sludge will be provided to the CONTRACTOR. There haven't been issues in the past with any solids at the WWTP that would prevent land application.
5. An EGLE Part 41 permit, and Barry/Eaton Co. SESC permits are needed, as well as local plumbing and electrical approval.
6. The spoils for RIB #3 must be placed in the fill area shown on Cover Sheet.
7. The CMU blocks on the existing sludge storage tank are existing.
8. The OWNER will pay for material testing and construction staking.
9. Temporary Field Office can be used by the ENGINEER's project representative and to host progress meetings.
10. The Notice to Proceed is expected to be issued 4 to 6 weeks after the Bid opening. Contract Time does not start until the Notice to Proceed is

Modifications to Specifications:

1. Section 40 91 00 Process Instrumentation: Delete the first occurrence of this section that appears in the Specifications (the one that is six (6) pages). The five (5) page section that follows it is the applicable section for this project.
2. Section 46 33 44:
 - a. 2.01.A.; Add Watson Marlow Qdos to the list of approved manufacturers.
 - b. 2.03.C.; Delete.

- c. 2.03.D.; Delete.
 - d. 2.03.H.; Delete.
 - e. 2.03.L.; Delete.
3. Section 46 53 53.2.04.B.2.; After “611 gpm” add “and a peak rate of 1,222 gpm with one (1) SBR tank decanting at a time.”

Modifications to Drawings:

- 1. Sheet M4: The existing 4” plug valves on the inlet of WAS Pump Nos 1 and 2 are to be re-used.
- 2. Sheet M8: (Not Re-Issued)
 - a. Slide gate in the Vactor Truck Dump Pad shall be a flush mounted and hand wheel operated Rodney Hunt Series A-121, Waterman A-250, or equal.

Please contact the project manager with any questions or comments on this addendum.

Respectfully submitted,

Williams & Works

Brandon Mieras, P.E.
Project Manager

Enclosures: None

Cc: All Plan Holders
Patricia Rayl, Village of Middleville
Alec Belson, Village of Middleville
Troy McDonald, Century A&E
File